

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Alpena
 (County)

		Located In			Corner Code #
1. Public Land Survey		T	32N	R 8E	M.C. N of M-6
		T		R	
2. Property Controlling in Section	S 13	T	32N	R 8E	2
	S	T		R	
3. Miscellaneous Property in Section	S	T		R	
	S	T		R	

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on January 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

2- G.L.O. This corner position was not established during the original government survey M.C. N of M-6 John Hodgson D.S. April 1840 used a 10" Cedar for meander post on the Southwest margin of lake.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

2- Established the Northeast corner of the Northwest quarter of the northeast quarter of section 13 per B.L.M. instructions for the subdivision of a section. M.C. N of M-6 Established a witness corner to the recorded meander corner established by John Hodgson D.S. in 1840. Set a 5/8" X 32" rered with P.S. cap 508.13 feet North of M-6 on the East line of section 13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2- Set 5/8" X 32" rered with P.S. cap #33981 Wit: 8" Maple S50°E 19.21' 5" Balsam N15°E 15.15' 4" Cedar S40°W 14.67' 4" Ash S85°W 18.29' Carsonite Post North 1±	M.C. N of M-6 Set 5/8" X 32" rered with P.S. cap #33981 Wit: 3" Cedar N04°W 9.62' 6" Cedar N30°E 1.09' 5" Cedar S50°W 7.15' 8" Cedar N66°W 21.08'
---	---

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-10-03

