

MAY 16 1987

1996 ALPENA COUNTY REMONUMENTATION CORNER

LIBER

2 PAGE 41

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena (County)

Located in:

Corner Code #

- 1. Public Land Survey T 32N R 9E B-11, (N 1/4, 31) Alpena Twp.
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

RECORDED ALPENA COUNTY MI.

JUL 22 11 07 AM '96

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 11, column B.

I, Thomas L. Fabis, in a field survey on May 9, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855: G.L.O. Resurvey by Josiah Knauer - Set post & referenced: (W. Birch 7 - S38E-11, Y. Pine 10 - N20W - 14).
1897: County Survey by Fred A. Rice - Deposited one brick & 2 horse shoes at stake.
1973: Survey (W.O.4-4721) by James Scott of R.S. Scott Engineering Co. - Does not describe corner but makes tie to Center of Section (2642.32').
1977: Survey Notes (W.O. 77118) by Farrier of Wilcox Associates - Found 1/2" iron rod. Does not witness but makes tie to A-11 and C-11.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found no corner monumentation. Set 1/2" iron rod using Farrier's Notes from 1977. Corner Position checks with James Scott Survey from 1973.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY PEER APPROVED 5/14/96


Out B. Lee

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set 3" dia. aluminum cap, stamped to identify the corner, over the 1/2" iron rod.

Set tag #31591 in the following reestablished witnesses:

- 22" Ash - S25W - 34.07'
10" Cedar - N40W - 52.34'
3" Cedar - N40E - 55.65'
4" Ash - S30E - 54.04'



Signed by Thomas L. Fabis

Date July 17, 1996

Surveyor's Michigan License No. 31591