

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Alpena Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T	<u>32 N</u>	R	<u>9 E</u>	<u>B-5</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	<u>7</u>	T	<u>32 N</u>	R <u>9 E</u>
	S	_____	T	_____	R _____
3. Miscellaneous Property in Section	S	_____	T	_____	R _____
	S	_____	T	_____	R _____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on January 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5	•	•											
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-5 Josiah Knauer, D.S. July 1855  
 Set quarter section post  
 Wit: Sugar 14 S58°W 21 links  
 Hemlock 4 N22°W 7 links

16- This corner position was not established during the original government survey.

December 1981 Duane A. Ankrom R.L.S. #21265 set the South quarter corner of section 7 by Proportionate Measurement while doing a survey for Consumers Power Co.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-5 Found and accepted a 1/2" bar with P.S. cap #21265 as set by Duane A. Ankrom. My single proportionate measurement position for this corner would place the corner some 28' North of the position established by Duane A. Ankrom's. I do not know if this position would better represent the original G.L.O. corner established in 1855. So I accepted Duane A. Ankrom's corner as found.

16- Found 1/2" rod with P.S. cap #21265

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 1/2" rod with P.S. cap #21265  
 Wit: 12" Maple clump N51°W 43.93'  
 10" Spruce S70°W 24.01'  
 10" Spruce S21°E 15.80'  
 10" Spruce S71°E 11.32'

16- 1/2" rod with P.S. cap #21265  
 Wit: 4" Balsam N53°W 6.63'  
 7" White Birch S60°W 8.11'  
 6" Twin Cedar N68°E 19.88'  
 10" Cedar N02°W 19.78'

Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 12-10-03

