

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
 Alpena \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                      |       |   |       |   |       |                |
|--------------------------------------|-------|---|-------|---|-------|----------------|
| 1. Public Land Survey                |       | T | 32N   | R | 9E    | A-1            |
|                                      |       | T | _____ | R | _____ | _____          |
| 2. Property Controlling in Section   | S 6   | T | 32N   | R | 9E    | M.C. E. of A-1 |
|                                      | _____ | T | _____ | R | _____ | _____          |
| 3. Miscellaneous Property in Section | S     | T | _____ | R | _____ | _____          |
|                                      | _____ | T | _____ | R | _____ | _____          |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on January 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1	●	●											
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

A-1 GLO- John Hodgson, D.S. April, 1840  
 Set post corner Townships 32 and 33 North  
 of Ranges 8 and 9 East  
 Wit: Tamarack 8 S52°E 36 Links  
 Tamarack 8 S49°W 37 Links

R.S. Scott 1954, Kelley Island Company property map set a  
 concrete monument at a cedar stake set in 1919  
 Wit: 3" Cedar South 6.35'  
 4" Cedar West 5.05'

M.C. E. of A-1 GLO- John Hodgson, D.S., April 1840 to  
 margin of Lake Huron a spruce 8 in. diameter for meander  
 post.  
 Wit: Balsam 8" N18°W 32 Links

R.S. Scott 1954, Kelley Island Company Property Map set a  
 concrete monument at an existing cedar stake.  
 Wit: 4" Birch N02°E 7.28'  
 5" Birch South 4.9'

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

A-1 Found 4" concrete monument and square cedar post  
 fitting Robert S. Scott #5058 1954 survey.

M.C. E. of A-1 Found 4" concrete monument and square  
 cedar post fitting by Robert S. Scott #5058 1954 survey.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-1 4" Concrete monument  
 Wit: \*5" Cedar S05°E 6.30'  
 \*8" Cedar S88°W 4.68'  
 4" Spruce N08°W 6.28'  
 3" Cedar N74°E 13.96'

\* Old witnesses by others

M.C. E. of A-1 4" Concrete monument  
 Wit: 4" Cedar N20°W 8.02'  
 3" Cedar S85°E 4.61'  
 3" Balsam S22°E 11.75'  
 6" White Birch S40°W 4.50'  
 Water edge- Lake Huron East 40±

Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 12-10-03

