

**SURVEY & REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:30

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1994 REMONUMENTATION	T 28N R 8W	E-3
Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

*Jean Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3					●								
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Nov. 12, 1994,  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
restored below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

E-3: Cor. common to Sec. 4, 5, 8 & 9, T28N-R8W,  
1850 GLO re-survey: set post, Y. Pine 20", S40W, 33, Y. Pine 18", N20E, 25  
3-8-02 & 8-17-11, W.S. Merrill, Co. Sur., visit iron cor. no accessories  
7-31-22, W.S. Merrill, Co Sur, iron, Y Pine 20, S40W, 33, Y Pine 18, N20E, 25  
Kalk Co Rd Comm, fd 1 X 3/4 rod, bolt in P.P., N14W, 31.35', S26W 47.90'  
C. Tuller, fd iron, fc pst S 24.65 tack, P.P. SW 48.0 tack, P.P. NW 32.5 tack  
12-72 to 5-83, Certificates of Survey, all fd 1/2" pipe: Gourdie Fraser &  
Assoc. (Lib. D, Pg 61-62), J.L. Fletcher (Lib. 1, Pg. 730), L.R. Feindt (Lib.  
163 Pg 408), A. Lennox (Lib. 2, Pg. 529), T.B. Smith (Lib. 2 Pg 705),  
Kalkaska Co Rd Comm (Phil Case), B.M. Jones (Lib. 2, Pg 766)  
8-30-89, E. Farrier, fd 3/4" x 1 1/4" rect. I.B. 5' S. C.L. rd, w/access.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3: Cor. common to Sec. 4, 5, 8 & 9, T28N-R8W,  
Found 3/4" x 1 1/4" rectangle iron bar raised w/1/2" iron & cap #33969  
"TEB" - pulled both & replaced w/5/8" x 18" R.B. & brass cap - 0.4' below  
grade (paved rd), no GLO witnesses were fd.  
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a  
careful and faithful reestablishment of the position of the original  
corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3: Cor. common to Sec. 4, 5, 8 & 9, T28N-R8W,  
Found 3/4" x 1 1/4" rectangle iron bar raised w/1/2" iron & cap #33969  
"TEB" - pulled both & replaced w/5/8" x 18" re-bar & brass cap - 0.4'  
below grade (paved rd);  
Fd nail - P. Pole - N10W, 31.32',  
Fd nail - 7" R. Pine - N37E, 76.58',  
Fd nail - P. Pole - S35W, 47.79',  
Fd nail - service pole S10E, 21.69',  
Centerline Plum Valley Rd. 5' North.

Recorded by *Eugene Farrier*

Date 12-22-94

Surveyor's Michigan License No. 24594

