

SURVEY & REMONUMENTATION

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:30

SECTION

CORNER RECORDATION CERTIFICATE
Requirement of Act 74, Mich. P.A. 1970

corners in

KALKASKA (County)	Located in:	Corner Code: #
1994 REMONUMENTATION		
Public Land Survey	T 28N R 8W	E-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
Property Controlling in Section	S ___ T ___ R ___	_____
Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Nov. 12, 1994

whereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the recent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

E-4: Cor. common to Sec. 8 & 9, T28N-R8W,
1850 GLO re-survey: set post, Sugar 12", N60E, 15, Hemlock 20", S51W, 20
6-3-1882, E. Mosher, visted corner, no accessories.
3-8-02 & 8-1-11, W.S. Merrill, Co. Sur., visit cor. no accessories
C. Tuller, shows iron on drawing, no accessories
6-55, G.A. Shadko, fd iron, no accessories
11-72 to 4-88, Certificates of Survey, all found 3/4" pipe, R.C. Dunn (Lib 1 Pg's 238 & 386), O.D. Love (Lib 1 Pg 669), A. Lennox (Lib 2 Pg 591, Lib 3 Pg's 166 & 215), B.M. Jones (Lib. 2, Pg's 542 & 539, Lib 3 Pg 69), E. Farrier (fd pk nail over 3/4" iron), T.B. Smith (Lib 3 Pg 205).
11-9-89 LCRC (E. Farrier), fd pk nail over iron, w/access., Lib 2 Pg 389

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4: Cor. common to Sec. 8 & 9, T28N-R8W,
East 1/4 cor. Sec. 8, T28N-R8W, fd 3/4" iron pipe. Pulled & replaced w/5/8" x 18" re-bar & brass cap 0.3' below bit rd surface in Mon. Box. No GLO were found.

On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.


Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4: Cor. common to Sec. 8 & 9, T28N-R8W,
East 1/4 cor. Sec. 8, T28N-R8W, fd 3/4" iron pipe. Pulled & replace w/5/8" x 18" re-bar & brass cap 0.3' below bit rd surface in Mon. Box.
Fd nail 6" Red Pine N35E, 33.83
Fd nail P. Pole S25E, 70.32
Fd nail P. Pole S84W, 108.72
Fd nail 11" Cherry clump N15W, 46.31



Surveyed by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 12-22-94