

SURVEY & REMONUMENTATION

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:30

SECTION

FIELD CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Joan Hall
REG. OF DEEDS

corners in

<u>KALKASKA</u> (County)	Located in:	Corner Code #
1994 REMONUMENTATION	T <u>28N</u> R <u>8W</u>	E-5
Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER, in a field survey on Nov. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the official manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as stated below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

E-5: Cor. common to Sec. 8, 9, 16 & 17, T28N-R8W, 1850 GLO re-survey: set post, Beech 20" N26W, 31, Maple 8" S16E, 41. 7-25-00, Unknown Co. Surv., no cor. nor witness fd, locate new post by int. lines between N1/4 post & NW cor of 17 and W1/4 post of 16 & 9 - wit: Hemlock stmp 27" S36 1/2 45' W 79' 3", W. Pine stmp 36" S3 1/2 50' W 78' 2". 3-8-02 & 8-1-11, W.S. Merrill, Co. Surv., visit cor., no accessories C. Tuller, fd cor., set 1 1/4" iron pipe, w/accessories 9-21-83, Kalkaska Co Rd Comm., fd buggy skein, w/accessories 7-26-86, E. Farrier, fd 1/2" pipe, w/access, raised w/1/2" re-rod 11-09-89, LCRC (E. Farrier), fd 1/2" pipe, w/accessories

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5: Cor. common to Sec. 8, 9, 16 & 17, T28N-R8W, Fd 1/2" iron pipe, over 1/8" x 3" met. band along side 1 1/4" iron pipe, that is 0.25' North of the raised 1/2" iron pipe, set 5/8" x 18" w/co. cap in the 1 1/4" iron pipe. Note: the 1 1/4" pipe appears as the same that C. Tuller set, that shows on map, no date. On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *[Signature]*
Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5: Cor. common to Sec. 8, 9, 16 & 17, T28N-R8W, Fd 1/2" iron pipe, over 1/8" x 3" met. band along side 1 1/4" iron pipe, that is 0.25' North of the raised 1/2" iron pipe, set 5/8" x 18" w/co. cap in the 1 1/4" iron pipe.
Fd nail in NW side 9" R. Pine, N60E, 57.41
Fd nail in SW side 10" R. Pine, S59E, 47.86
Fd nail in SE side 11" Tw. Oak S42W, 97.14
Fd nail in 19" Maple, S40W, 134.92

Recorded by *[Signature]*
Surveyor's Michigan License No. 24594

Date 12-12-94

