

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:30

Joan Hall
REG. OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1994 REMONUMENTATION		
Public Land Survey	T <u>28N</u> R <u>8W</u>	<u>E-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

EUGENE FARRIER, in a field survey on Nov. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

RE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 6: Cor. common to Sec. 16 & 17, T28N-R8W, 1950 GLO re-survey: set post, W. Pine 6", N64W, 29, Sugar 6", S40E, 9, 1925-00, Unknown Co. Surv., fd stake and original accessories
- 1927-79 & 6-26-80, A.L. Drago, fd cor. 1/2" pipe, w/accessories, Lib. Pg's 495, 496 & 563
- 1921-83, Kalkaska Co Rd Comm., fd cor. 1/2" pipe, w/accessories
- 1926-86, E. Farrier, fd 1/2" pipe, w/accessories.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 6: Cor. common to Sec. 16 & 17, T28N-R8W, 1/4 cor. Sec. 16, T28N-R8W, fd 1/2" iron pipe raised with 1/2" iron & p #24594 "EDF", pulled both & replaced with 5/8" x 18" re-bar & brass p, 0.6' below gravel road. No GLO witnesses were found.
- 12-20-94 the Kalkaska Co. peer group approved the above monument as a lawful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *Eugene Farrier*
Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 6: Cor. common to Sec. 16 & 17, T28N-R8W, 1/4 cor. Sec. 16, T28N-R8W, fd 1/2" iron pipe raised with 1/2" iron & p #24594 "EDF", pulled both & replaced with 5/8" x 18" re-bar & brass p, 0.6' below gravel road.
- nail - 10" W. Pine, N47W - 61.20'
- nail - 12" W. Pine, N62E - 46.56'
- nail - P. Pole, S14E - 100.90'
- nail - 12" W. Pine - S43W - 56.03'
- corner falls in centerline Round Lk Rd.

Recorded by *Eugene Farrier* Date 12-22-94
Surveyor's Michigan License No. 24594

