

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

SECTION

LAND CORNER RECORDATION CERTIFICATE 1994 DEC 23 AM 9:30
Filing Requirement of Act 74, Mich. P.A. 1970

corners in

KALKASKA (County)	Located In:	Corner Code #
1994 REMONUMENTATION		
Public Land Survey	T 28N R 8W	E-8
	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
	S T R	
Miscellaneous Property in Sec.	S T R	

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

EUGENE FARRIER, in a field survey on Nov. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the recent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- E-8: Cor. common to Sec. 20 & 21, T28N-R8W
- 1850 GLO re-survey: set post, Beech 10", S40W, 36, Hemlock 12", N70E, 32
- 7-2-1879, D.E. McVee, noted cor., no accessories
- 6-8-73, LCRC(J.H. Granger), fd wood post, w/accessories, Lib 1 Pg 235
- 8-17-73, J.H. Granger, fd post, w/accessories, Lib 1 Pg 356
- 5-10-84, E. Farrier, note cor., no accessories

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8: Cor. common to Sec. 20 & 21, T28N-R8W
 Fd 10" Cedar post split & laying on ground. Fd remains of post in hole in ground. Set 5/8" x 36" R.B. w/alu. cap 0.4 above ground surface in center of hole. No GLO witnesses were fd.
 Note: Looked for wit. on certificate of survey recorded on Liber 1 Page 356. None were fd. On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman *Eugene Farrier*
 Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-8: Cor. common to Sec. 20 & 21, T28N-R8W
- Fd 10" Cedar post split & laying on ground. Fd remains of post in hole in ground. Set 5/8" x 38" R.B. w/alu. cap 0.4 above ground surface in center of hole.
- Set nail & tag S43W, 14" W. Pine, 5.70'
- Set nail & tag N21E, 3" W. Pine, 22.92'
- Set nail & tag N50E, 5" W. Pine, 9.57'
- Set nail & tag S64E, 6" W. Pine, 10.06'



by *Eugene Farrier*
 Surveyor's Michigan License No. 24594

Date 12-23-94