

**SURVEY & REMONUMENTATION**

MAY 10 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:31

*Joan Hall*  
REG. OF DEEDS

corners in

|                             |                          |                |
|-----------------------------|--------------------------|----------------|
| <u>KALKASKA</u><br>(County) | Located In:              | Corner Code #/ |
| 1994 REMONUMENTATION        |                          |                |
| Public Land Survey          | T <u>28N</u> R <u>8W</u> | <u>F-5</u>     |
|                             | T _____ R _____          | _____          |
|                             | T _____ R _____          | _____          |
|                             | T _____ R _____          | _____          |
| Property Controlling        | S _____ T _____ R _____  | _____          |
| In Section                  | S _____ T _____ R _____  | _____          |
| Miscellaneous               | S _____ T _____ R _____  | _____          |
| Property in Sec.            | S _____ T _____ R _____  | _____          |

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

EUGENE FARRIER, in a field survey on Nov. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- F-5: Cor. common to Sec. 9 & 16, T28N-R8W.
- 1850 GLO re-survey: set post, Beech 14" N49E, 38, Sargar 12" S10W, 26.
- 7-25-00, Unknown Co Sur., fd iron sleigh shoe, no accessories
- 3-8-02 & 8-1-11, W.S. Merrill (Co. S.), visit cor-no ident., no access.
- 10-26-16, Chessie Sys. R.R., note pipe for cor. on draw., no accessories
- 6-55, G.S. Shadko, fd 3/4" iron, no accessories
- 8-6-72, R.C. Dunn, notes cor., no accessories, Lib. 1, Pg 162
- 7-11-73, Gourdie Fraser & Assoc., fd cor., no accessories
- 9-19-75, C.J. Hughes, fd 3/4" pipe, w/ accessories, Lib 1 Pg 969
- 9-28-84, E. Farrier, notes cor., no accessories
- 9-20-91, B.M. Jones, fd 5/8" iron, w/accessories, Lib 4 Pg 40

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5: Cor. common to Sec. 9 & 16, T28N-R8W.  
Fd 5/8" bolt 6" long & axel shaft 3' long & leaf spring 3' long. Pulled & replaced with 5/8" x 18" Re-bar & brass cap 0.42 below rd bit surface. No GLO witness were fd. Set Mon. Box.  
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*  
Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-5: Cor. common to Sec. 9 & 16, T28N-R8W.
- Fd 5/8" bolt 6" long & axel shaft 3' long & leaf spring 3' long. Pulled & replaced with 5/8" x 18" re-bar & brass cap 0.42 below rd bit surface. Set Mon. Box.
- Fd nail P. Pole S54W 31.12
- Fd nail P. Pole N10W 86.97
- Fd nail P. Pole N54E 40.14
- Fd nail P. Pole S05E 118.62



Surveyed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 12-22-94