

**SURVEY &  
REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN  
RECEIVED

1994 DEC 23 AM 9:31

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

*Jean Hall*  
REG. OF DEEDS

corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1994 REMONUMENTATION		
Public Land Survey	T <u>28N R 8W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Nov. 12, 1994,  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- G-10: Cor. common to Sec. 27 & 28, T28N-R8W.
- 1850 GLO re-survey: set post, Beech 14" S53E, 27, Beech 14" N33W, 45
- 1-6 & 6-15-1876, D.E. McVee (Co. Surveyor), noted cor., no accessories
- 1889, E. Mosher, noted cor. no accessories
- 1902-1915, W.S. Merrill, noted cor. several times, no accessories
- 6-8-73, LCRC (J.H. Granger), fd 1 1/2" iron, w/accessories
- 4-6-81, E. Farrier, fd 1/2" rod, w/accessories
- 4-15-86, LCRC (E. Farrier), fd 1/2" rod, w/accessories, Lib 2 Pg 298
- 11-14-89, LCRC (B.M. Jones), fd 1/2" rod, w/accessories
- 11-14-89, B.M. Jones, fd 1/2" rod, w/accessories

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10: Cor. common to Sec. 27 & 28, T28N-R8W.  
Fd 1/2" iron 2' E. C.L. gravel rd. Pulled & reset with 5/8" x 18" re-bar &  
brass cap 0.6' below rd surface. No GLO witnesses were fd.  
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a  
careful and faithful reestablishment of the position of the original  
corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*  
Date 12-22-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-10: Cor. common to Sec. 27 & 28, T28N-R8W.
- Fd 1/2" iron 2' E. C.L. gravel rd. Pulled & reset with 5/8" x 18" re-bar &  
brass cap 0.6' below rd surface.
- Fd nail 12" Ashe, N70W, 26.19'
- 1/2" iron, East 33.00'
- Fd nail 12" Tri-Poplar, S08E, 65.54'
- Fd nail 8" Poplar, S59W, 32.31'

Witnessed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 12-22-94

