

**SURVEY & REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:31

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

or corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1994 REMONUMENTATION		
Public Land Survey	T <u>28N</u> R <u>8W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

*Jean Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER, in a field survey on Nov. 12, 1994,  
thereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

G-12: Cor. common to Sec. 33 & 34, T28N-R8W.  
1850 GLO re-survey: set post, Sugar 5" N66W, 22, Sugar 6" S55E, 31  
9-16-1880, G. Alinepert, noted cor., no accessories  
8-11-02, W.S. Merrill, fd stmp & old stk., set new iron stk., w/access.  
4-6-09, W.S. Merrill, noted iron at cor., no/accessories  
11-4-71, LCRC(J.L. Fletcher), fd 1 1/4" iron, w/access, Lib 2 Pg 133  
1-5-77, LCRC(H.L. Fluharty), fd 1 1/4" iron, w/access, Lib 2 Pg 5  
5-8-90, LCRC(E. Farrier), fd 1 1/4" iron, w/access, Lib 2 Pg 414  
6-73 to 4-90 Certificates of Survey, all fd 1 1/4" iron, R.C. Dunn(Lib 1 Pg 385), H.L. Fluharty(Lib 2 Pg 622, Lib 1 Pg 952), T.J. Mueller(Lib 2 Pg 318), Phil Case(fd iron w/witness), E. Farrier(witness rec'd Lib 1 Pg 537), Kalkaska Co Rd Comm(w/witness), J.L. Wilcox(Lib 3 Pg 140)

b. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12: Cor. common to Sec. 33 & 34, T28N-R8W.  
Fd 1 1/4" pipe w/spike in middle. Pulled & replaced with 5/8" x 36" re-bar w/alu. cap 0.8 below ground surface. No GLO witnesses were fd. On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful perpetuation of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Description of monument for corner and accessories established to perpetuate locating the Date of the corner: 12-20-94

G-12: Cor. common to Sec. 33 & 34, T28N-R8W.  
Fd 1 1/4" pipe w/spike in middle. Pulled & replaced with 5/8" x 36" re-bar w/alu. cap 0.8 below ground surface.  
Fd nail S30W Triple Maple, 54.35  
Fd nail S85W, 12" Maple, 50.39  
Fd nail N54W 14" Maple, 49.55



Witnessed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 12-22-94