

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--				CORNER CODE NUMBER	
	T.	N. S.	R.	E. W.	A-3 A-4	A-5 B-4
1. PUBLIC LAND SURVEY	T. 28	N. S.	R. 8	E. W.		
2. PROPERTY CONTROLLING IN SECTION	T. _____	N. S.	R. _____	E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____	N. S.	R. _____	E. W.		
4. LOT NO. _____, RECORDED PLAT _____						
5. PRIVATE CLAIMS _____						

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12-28 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-3 Found 3/4" x 24" pipe by corner fence post. Old accepted corner.
- A-4 Recovered pipe by old corner fence post, fence N & W. Accepted for proper 1/4 corner. Fits 1/8 corner & section corner South
- A-5 Recovered 1"x36" pipe, old corner of record. Merrill 1923, had Govt. Bearing Trees.
- B-4 Established corner at intersection of 1/4 lines per std. B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3			A-5		
Found pipe, added DNR con.mon W/St fn post			Fd pipe, added DNR con.mon w/st fn. post		
10" Maple	N57W	13.2'	8" Red Pine	S73W	35.3'
9" Oak	N60E	35.3'	8" Hemlock	N35W	16.3'
9" Maple	S37W	32.2'	10" Red Pine	S49E	20.2'
A-4			B-4		
Fd. Pipe, added DNR Con.mon W/st fn. post			Set DNR Conc. mon W/St. fn. post.		
12" Maple	N47W	18.6'	7" Cedar	N87W	24.7'
14" Oak	S88E	39.8'	4" Cedar	S71E	20.5'
13" Oak	S56E	34.7'	6" Tamarack	N40W	15.8'


SIGNED BY Carl F. Roser DATE 6-15-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____