

FEB 18 1999

159-160

Liber 00003 Page 0019

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY MI.
Register of Deeds
Recorded

12-15-1998 10:16:02

Wanda R. Conway
REGISTER OF DEEDS

For corners in

MILTON

Antrim (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. 35 T 29N R 9W	K-13
	Sec. 2 T 28N R 9W	K-1
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Terry B. Smith, in a field survey on 12-10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO wood post circa 1853
 County Surveyor's notes circa 1901
 Certificate N. Way 1998, 1997
 certificate B. Jones 1981
 certificate James Fletcher 1974
 certificate A. Lennox 1978, 1979
 LCRC J. Fletcher L. 219 pg. 580

Ratified by peer group
 in accordance with
 P.O. 345
 Antrim Co. Chairman

Arthur L. Lennox
 Arthur L. Lennox
 Nov. 18, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found 1/2" steel bar in center line intersection
 excavation revealed a "gear shaft" per call of Antrim County Surveyor's notes
 circa 1901. Witnesses circa 1901 gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Antrim county Monument and highway box
 24" Maple S65W 81.10
 UP N15W 89.74
 UP N51E 43.68
 UP S42W 44.28



Signed by *T.B. Smith*
 Surveyor's Michigan License No. 25873

Date DEC. 14, 1998