

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 29 N N.R. 4 W *- need folder*
T. 29 N N.R. 5 W ✓ Antrim
Otsego COUNTY

DESCRIPTION OF CORNER Sec. corner common to sections 7-8-12-13

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 22, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

36" W. Pine stump S 62 E 30.3'

20" W. Pine Stump N 26 E 12.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportionate measurement between good $\frac{1}{4}$ corner south and town corner north where we found stake bottom faced by 2 very old MBTs. Checks swamp edge east very well, and north acceptably.

SURVEYOR'S SEAL

SIGNED Kenneth Ostling DATE August 10, 1966
REGISTERED LAND SURVEYOR #10068