

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 N.R. 5 W


Antrim COUNTY

DESCRIPTION OF CORNER Sec. corner common to sections 14-15-22-23

CORNER MONUMENT Left 3/4" O.D. pipe in place 4" below surface of road

DATE MONUMENT PLACED AND WITNESSED May 12, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" B. Cherry N 28 W 53.2'

2" R. Pine S 26 W 63.6'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of the S $\frac{1}{2}$ of this township. Found pipe in place probably as established in early survey by county surveyor. No record, or no U.S. evidence left. Best available evidence of proper location for corner.

Falls about 4' south of centerline of E-W county road.

SURVEYOR'S SEAL

SIGNED *Lucretia J. Ostling* DATE May 17, 1966
REGISTERED LAND SURVEYOR 710068