

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 N.R. 5 W


Antrim COUNTY

DESCRIPTION OF CORNER Sec. corner common to sections 11-12-13-14

CORNER MONUMENT Set 1" pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED July 22, 1966

WITNESSES TO CORNER.....



40" W. Pine stump S 10 E 29.6'

40" W. Pine stump N 52 W 41.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey of Section 13. Set corner at the intersection of lines parallel with the south and east lines of Section 13. This procedure was adopted as last resort, after extensive survey to recover controlling corners to north and west. Nothing to be found within four miles west or north. Mostly Ward Land Company holdings with little occupation, or evidence of previous survey. Considered the only practical solution.

SURVEYOR'S SEAL

SIGNED *Kenneth Ostberg* DATE August 10, 1966
REGISTERED LAND SURVEYOR #10068