

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5. W. . . .

----- Antrim -----

----- COUNTY

DESCRIPTION OF CORNER Corner common to Sections 33 & 34 on south boundary of township.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

7" Cherry - S75E - 95 links

9" Aspen - N3E - 154 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between corners 1 mile west and 3 miles east by Forestry Division survey crew while making a survey of the south half of this township. An old scribed stake is 223 links south and 45 links east but could find no NBTs or evidence of original BTs. Stake was disregarded in our attempt to fix the entire south line of this township.

Closing corner for Sections 3 & 4, T28N R5W is 15 links west.

Corner was placed and witnessed April 9, 1957.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 5/13/57