

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5. W. . .

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side of Section 31, on  
south boundary of township.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER -----

7" Cherry - N86E - 70 links

5" Cherry - N52W - 84 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

This corner was established by proportionate measurement  
between section corners by Forestry Division survey crew while  
making a survey of the south 1/2 of this township.

Corner was placed and witnessed April 4, 1957.

1/4 corner for Section 5, T28N R5W is 6 1/2 links west.

SURVEYORS SEAL

SIGNED Billy D. Buckles  
REGISTERED LAND SURVEYOR

DATE 5/13/57