

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR 5. W. . . .

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Corner common to Sections 31 & 32 on south
boundary of township.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER -----

7" Cherry - N29W - 13½ links

7" cherry - N47E - 94½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by Forestry Division survey
crew while making a survey of the south half of this township.
Corner was established by proportionate measurement between
corners 1 mile east and 1 mile west.

Closing corner for Sections 5 & 6, T28N R5W is 13 links west.

Corner was placed and witnessed April 9, 1957.

SURVEYORS SEAL

SIGNED

Billy D. Buckley
REGISTERED LAND SURVEYOR

DATE 5/13/57