

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5. W. . .

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Corner common to Sections 32 & 33 on south  
boundary of township.  
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

8" Aspen	-	N50W	-	58½ links
7" Cherry	-	N52E	-	26½ links

-----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

This corner was established by Forestry Division survey crew while making a survey of the south half of this township. Corner was established in center of N-S fireline for longitudinal position to best conform with existing occupation without too much departure from government measure. Latitudinal position is on line between town corner east and west. This action was supported in an opinion of the Chief Cadastral Engineer with the Bureau of Land Management. See Minutes of Survey for other information.

Closing corner for Sections 4 & 5, T28N R5W is 13 links west

Corner was placed and witnessed April 8, 1957.

SURVEYORS SEAL

SIGNED

*Billy D. Buckles*  
REGISTERED LAND SURVEYOR

DATE 5/13/57