

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 NR 5 W --
T29 NR 5 W --
T28 NR 6 W --
T29 NR 6 W --

----- Antrim -- Kalkaska - COUNTY

DESCRIPTION OF CORNER Corner common to Sections 1, 6, 31, 36
Towne 28 & 29 north, Ranges 5 & 6 West

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" Maple - S46E - 39 links
6" Maple - N24E - 49 links
5" Maple - S85W - 40½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by Forestry Division survey crew while making a survey of the S1/2 of T29N R5W. No conclusive original evidence could be found at this corner. After considerable research it was established by double proportionate measurement between corners 1 mile north, 2 miles south, 3 miles west, and 2 miles east.

Corner was placed and witnessed April 8, 1957.

SURVEYORS SEAL

SIGNED *Billy D. Buckles* DATE 5/13/57
REGISTERED LAND SURVEYOR