

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5 W.

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19, 20, 29, 30 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

9" Basswood - S6W - 26 links -----

4" Maple - N73W - 37 links -----

4" Ironwood - N37E - 8 $\frac{1}{2}$ links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement by Forestry Division survey crew while making a survey of the S 1/2 of this township. Corners 1 mile west, 1 mile east, 1 mile north and 2 miles south were used in the proportion. A old E - W road grade is about 40 links north.

Corner was placed and witnessed June 6, 1957

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/26/57
REGISTERED LAND SURVEYOR