

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 NR. 5 W.

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 20 & 21

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER -----

5" Aspen - N33E - 57 links

36" W. Pine stump S34E - 63 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement by Forestry Division survey crew while making a survey of the S 1/2 of this township. Set midpoint, on line between section corners north and south. Falls in west edge of N - S fireline.

Corner placed and witnessed June 6, 1957

SURVEYORS SEAL

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 2/26/57