

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5 W. . .

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 20, 21, 28, 29 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

7" Aspen - N2W - 21 1/2 links -----

6" Aspen - S63E - 30 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey of the S 1/2 of this township. Set by single proportionate measurement between section corners 1 mile north, and 1 mile south, to establish control for E - W proportion. A 1/2" pipe with concrete is 58 links north and 88 links west, but has no supporting evidence and makes east and south line of Section 20 far too short. Possibly corner to old unrecorded plot.

Corner was placed and witnessed June 6, 1957

SURVEYORS SEAL

SIGNED Billy D. Buchler DATE 7/26/57  
REGISTERED LAND SURVEYOR