

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 NR. 5 W.

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 21, 22, 27, 28

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

6" Aspen - S16W 79 links

No other worth noting

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between section corners 1 mile north, 2 miles south, 1 mile west and 3 miles east by Forestry Division survey crew while making a survey of the S 1/2 of this township.

Corner was placed and witnessed June 17, 1957

SURVEYORS SEAL

SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 2/26/57