

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5. W. . .

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Corner common to Sections 28, 29, 32, 33
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER -----

7" Cherry - N22E - 57½ links
5" Cherry - S45E - 63 links
6" Cherry - S30W - 40½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey of the S1/2 of this township. This corner was set by proportionate measurement for latitude, and in center of N-S fireline for longitude to conform with man-made boundary. This point would conform fairly well with an east-west proportion but was held to the fireline for better identification of boundary. This concurs with an opinion of the Cad. Engineer for the Bureau of Land Management.

Corner was placed and witnessed April ~~xx~~ 9, 1957.

SURVEYORS SEAL

SIGNED Billy D. Snodgrass DATE 5/13/57
REGISTERED LAND SURVEYOR -----