

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5. W. . .
T 29 NR 6 W

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Corner common to sections 30, 31, 25, 36 T29N R5&6W

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

6" Elm	-	S2W	-	48½ links
8" Elm	-	N60W	-	37 links
8" Elm	-	N22E	-	104½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey of the S1/2 of T29N R5W. Found a 3/4" pipe in centerline of old road grade from north and trail east. No evidence of OBTs, but apparently was used in locating a 1/4 corner north, and was accepted as the corner to these sections. Placed our corner at pipe, below surface of ground.

Corner was placed and witnessed April 25, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 5/13/57
REGISTERED LAND SURVEYOR