

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5. W. . .

----- Antrim -----

----- COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side Section 34 on south boundary of township.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER -----

5" Cherry - N8W 159 links

5" Cherry^m - N69E 170½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey of the S 1/2 of this township.

1/4 corner for Section 3, T28N R5W is 12½ links west.

Corner was placed and witnessed April 22, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckley
REGISTERED LAND SURVEYOR

DATE 5/13/57