

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 29 NR 5 W
T 29 NR 6 W

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 25 & 30
T29N R5&6W
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER -----
8" Cherry - N15W - 107 links

8" Cherry - S60W - 38½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey of the S1/2 of T29N R5W. Found a 3/4" pipe at midpoint and on line between section corners north and south. Also an old stake bottom. No evidence of OBTs, but was accepted as the 1/4 corner for lack of evidence to the contrary.

Corner was placed and witnessed April 26, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 5/13/57
REGISTERED LAND SURVEYOR