

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 29 .. NR .. 5 W ..

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22, 23, 26, 27 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

8" Aspen - N20W - 125 $\frac{1}{2}$  links -----

40" W. Pine stump N84E - 47 $\frac{1}{2}$  links -----

20" W. Pine stump S4E - 31 $\frac{1}{2}$  links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between section corners 1 mile north, 2 miles south, 2 miles east, and 2 miles west by Forestry Division survey crew while making a survey of the S 1/2 of this township. No positive evidence of White Pine witness.

Corner was placed and witnessed June 17, 1957

SURVEYORS SEAL

SIGNED Billy D. Buckley DATE 7/20/57  
REGISTERED LAND SURVEYOR