

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 5 W.

----- Antrim ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 29, 30, 31, 32

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER -----

7" Cherry - S51E - 59 links

6" Cherry - S9W - 99 links

6" Cherry - N61W - 144 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 1 mile east, 1 mile west, 1 mile south and 2 miles north, by Forestry Division survey crew while making a survey of the S 1/2 of this township.

Corner was placed and witnessed June 10, 1957

SURVEYORS SEAL

SIGNED Billy D. Buckley DATE 7/26/57
REGISTERED LAND SURVEYOR