

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Antrim</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 29N R 5W	H-5
	T 29N R 5W	I-5
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on July 15, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5 GLO set quarter section post - J.H. Mullett - 1839.
 Wit: Beech 12" S 26° W 15 links
 Sugar 12" S 38° E 10 links

I-5 GLO set post - J.H. Mullett - 1839.
 Wit: Beech 12" N 45° W 28 links
 Sugar 16" N 50° E 22 links

Valley Ridge Heights West Surveyor placed a 1/2" bar for the quarter corner c. 1970.

Valley Ridge Heights West Surveyor placed a concrete monument for the section corner c. 1970.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 Found a 1/2" bar fitting the Plat of Valley Ridge Heights West.

I-5 Found a concrete monument fitting the Plat of Valley Ridge Heights West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 Set 1" x 32" iron pipe with aluminum DNR monument cap and set carsonite marker post.
 Wit: * Nail set in 10" triple Maple N 41° E 14.93'
 * Nail set in 4" Maple S 14° W 6.81'
 * Nail set in 10" triple Maple S 54° W 16.26'
 Set nail in 10" triple Maple N 32° W 57.19'
 1/2" iron rod East 20.05'

I-5 Found concrete plat monument.
 Wit: Set nail in 7" Maple S 50° W 11.81'
 Set nail in 8" triple Maple N 72° W 34.98'
 Set nail in 3" Cherry S 8° E 27.09'
 Set nail in 7" twin Maple N 13° E 45.67'

* (Old witnesses by others.)

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981



Date 8-18-99