

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Antrim _____
 (County)

1. Public Land Survey		T	<u>29</u>	R	<u>6W</u>	<u>M-12</u>
		T	<u>29</u>	R	<u>6W</u>	<u>M-13</u>
2. Property Controlling in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____
3. Miscellaneous Property in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on September 20, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-12 GLO-H. Brevoort & J. H. Mullett D.S.- 1839
 Set ¼ Section Post
 Wit: Hemlock 30 S55°W 16 Links
 Hemlock 30 N82°W 18 Links

Kenneth J. Ostling R.L.S. #10068 April 1957
 Set 1" pipe with 4" brass cap by single proportionate measurement.
 Wit: 8" Elm N66°W 64.5 links
 7" Elm N50°E 92 links

M-13 H. Brevoort & J. H. Mullett D.S.- 1839
 Post Corner Townships 28 & 29 North
 Ranges 5 & 6 West
 Wit: Sugar 12 N01°E 11 Links
 Elm 12 N67°W 20 Links

Kenneth J. Ostling R.L.S. #10068 April 1957
 Set 1" pipe with 4" brass cap by double proportionate measurement
 Wit: 6" Maple S46°E 39 links
 6" Maple N24°E 49 links
 5" Maple S85°W 40.5 links

Peter E. Chenard R.L.S. #14200 Sept. 1972 Found 1" pipe and Dept. of Conservation brass cap
 Wit: West 7" Maple 26.35', N30°E 9" Maple 32.15', S45°E 9" Maple 25.65'

Daniel E. Schripsema R.L.S. #24617 Oct. 1999
 Found DNR monument.
 Wit: S40°W 16" Twin Maple 6.01', S37°E 8" Maple 10.55', N47°E 10" Maple 15.35', N06°E 12 Maple 15.76'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-12 Found D.N.R. monument.

M-13 Found D.N.R. monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Found DNR Monument
 Wit: * 14" Elm N58°W 42.96'
 6" Elm N38°E 29.27'
 8" Cherry S59°W 40.18'
 18" Maple S20°E 71.11'
 Carsonite Post North 1'±
 Ctr. N-S Trail Road East 54'±

M-13 Found DNR Monument
 Wit: * 5" Maple N10°E 15.76'
 * 4" Maple N69°E 15.29'
 * 10" Maple S41°E 25.91'
 * 8" Maple N83°W 26.41'
 Carsonite Post North 1'±

*Old Witness By Others

*Old Witness By Others

Signed by: Carl T. Kiiskila

Date: 4-16-02

Surveyor's Michigan License No.: 33981

