

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Antrim (County)	Located In	Corner Code #
1. Public Land Survey	T <u>29</u> R <u>6W</u>	<u>K-11</u>
	T <u>29</u> R <u>6W</u>	<u>K-12</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on October 18, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

K-11 GLO H. Brevoort & J.H. Mullett D.S. – 1839  
Set Post Corner Section 25, 26, 35 & 36  
Wit: Beech 18 N66°W 35 Links  
Beech 14 N19°E 10 Links

K-12 GLO H. Brevoort & J.H. Mullett D.S. – 1839  
Set ¼ Section Post  
Wit: Beech 12 N13°W 41 Links  
Lynn 16 S62 ½ °E 11 Links

Beryl M. Jones RLS #23514 Sept. 1981 LCRC L.2 P. 74  
Found 1" square bar Wit: East 5" Poplar 24.27', S50°W 12"  
Poplar 11.57', S50°W 12" Poplar 11.57'

David G. Heydlauff RLS #32337 Oct. 1999 Cert. of Survey  
L. 530 P. 671 "Found iron bar w/ cap #20706  
Wit: N63° 19'.83' Maple 12", S45°W 9.95' Ash 10", S87°W  
24.59', Maple 24", N41°W 13.19' Maple 12"

David G. Heydlauff RLS #32337 Oct. 1999 Cert. of Survey L.  
530 P. 671 Found 1" X 1 ½" square iron bar Wit: S86°E  
30.53' P. Pole, S04°E 17.62' Poplar, S72°E 6.65' Guy Pole,  
S82°W 20.76' Cherry 8"

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

K-11 Found 1x 1½ Rectangular Bar

K-12 Found ½" Rod w/PS Cap #24600 & #20706

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-11 Found 1x 1½ Rectangular Bar  
Wit: \*Power Pole S75°E 6.65'  
3" Cherry S30°W 41.56'  
\*5" Cherry S84°W 20.81'  
\*Power Pole S86°E 30.55'  
Carsonite Post North 1'±  
Ctr. N-S Road East 22'±

K-12 Set DNR Monument  
Wit: \* 8" Maple N63°E 19.88'  
\* 8" Basswood S47°E 9.97'  
\*18" Maple S88°W 24.55'  
\*10" Maple N41°W 13.19'  
Carsonite Post North 1'±

\*Old Witness By Others

Signed by: Carl T. Kiiskila  
Surveyor's Michigan License No.: 33981

Date: 4-16-02

