

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Antrim (County)	Located In	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>6W</u>	<u>L-9</u>
	T <u>29N</u> R <u>6W</u>	<u>M-9</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

I, **Carl T. Kiiskila**, in a field survey on **September 10, 2000** do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9 GLO – H. Brevoort & J.H. Mullett D.S. – 1839
Set Quarter Section Post
Wit: Birch 10 S68°E 17 Links
Sugar 18 N31°W 10 Links

M-9 GLO – H. Brevoort & J.H. Mullett D.S. – 1839
Set Post Corner 24 & 25
Wit: Hemlock 14 S50°W 12 Links
Beech 18 N48°W 26 Links

Beryl M. Jones L.S. # 23514 Aug. 1990 Cert. of Survey L. 401 P. 227 "Found "T" iron" Wit: N25°W 8" Cherry 46.45', N50°E 8" Cherry 63.35', S75°W Cherry clump 85.74', S24°W metal fence post 40.80'

Beryl M Jones L.S. #23514 Aug. 1990 Cert. of Survey L. 401 P. 227 "Found DNR Mon." Wit: N52°E P. Pole 52.80', N83°E 10" Cherry 66.25', S10°E 9" Cherry 65.90', S32°W 3" Poplar 112.60'

Beryl M. Jones L.S. #23514 Aug. 1995 Cert. of Survey L. 431, P. 1321 "Found "T" iron" Wit: same as above

Beryl M. Jones L.S. 23514 Aug. 1995 Cert. of Survey L. 431 P. 1321 "Found DNR Mon." Wit: S30°W 14" Poplar 113.06', S08°E 18" Cherry 85.11', S60°E 12" Cherry 82.20', N82°E 20" Cherry 66.77'

Terry B. Smith L.S. 25873 Aug. 1984 Cert. of Survey L. 290 P. 1089 "Found "T" iron Wit: 10" Cherry N50°E 63.6', 8" Cherry N30°W 46.5', 12" triple Cherry S55°W 85.4'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L-9 – Found Bent "T" Iron

M-9 – Found ¾" Iron Pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 – Set 5/8 x 32 Rerod w/PS Cap #33981
Wit: 7" Cherry N36°W 72.53'
14" Triple Cherry S70°W 85.79'
Power Pole South 34.19'
8" Cherry N35°E 72.82'

M-9 – ¾" Iron Pipe
Wit: Power Pole N58°E 53.98'
12" Cherry S62°E 82.17'
8 "Twin Cherry S07°E 85.20'
12" Poplar S29°W 113.11'
12" Cherry N84°E 66.77'

Signed by:

Carl T. Kiiskila

Date:

4-16-02

Surveyor's Michigan License No.:

33981

