

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Antrim _____ Located In _____ Corner Code # _____
 (County)

1. Public Land Survey		T	<u>29N</u>		R	<u>6W</u>		I-13
		T	<u>29N</u>		R	<u>6W</u>		I-12
2. Property Controlling in Section	S	T			R			
	S	T			R			
3. Miscellaneous Property in Section	S	T			R			
	S	T			R			

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on September 18, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-12 G.L.O. H. Brevoort and J.H. Mullet D.S. 1839
 Set quarter section post
 Wit: Sugar 14 N31°E 10 links
 Sugar 12 N88°W 8 links

I-13 G.L.O. H. Brevoort and J.H. Mullet D.S. 1839
 Set post for sections 34 and 35
 Wit: Sugar 12 N13°W 21 links
 Sugar 12 N41°E 27 links

Gosling Czubak associates reset 1/2" X 18" iron from survey data by Perla Stout assoc.
 Wit: 4" Maple S25°E 12.9'
 8" Maple N45°E 8.4'
 6" Maple S60°W 26.8'

Gosling Czubak associates found a 1 1/4" gas pipe May 9, 1984
 Wit: 12" Yellow Birch S80°E 23.40'
 12" Maple N85°W 19.45'
 7" Maple N05°E 24.73'

Richard J. Kral P.S. #26460 found 1" pipe while doing a survey in the section 2 T28NR6W.
 Wit: N03°E 8" Maple 24.60'
 S70°E 6" Maple 12.00'
 S08°E 8" Maple 25.46'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

I-12 Found a 1/2" rod with P.S. #20357 and P.S. #25873 cap I-13 Found 1" iron pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Found 1/2" Capped iron
 Wit: *8" Maple N54°E 8.61'
 *4" Maple S17°E 13.10'
 *6" Maple S73°W 26.78'
 *6" Maple N62°W 27.01'
 1 1/4" iron pipe North .2'
 Old Fence East & West
 Intersection of trail Roads
 North, South & East, West East 150±
 *Old witnesses by others

I-13 Found 1" iron pipe
 Wit: *12" Yellow Birch S60°E 23.32'
 *9" Maple N07°E 24.51'
 *18" Maple N78°W 19.36'
 *10" Maple S06°W 25.43'

*Old witnesses by others

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 4-16-02

