

JAN 27 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Antrim (County)

Located In:

Helena Twp. Corner Code #

1. Public Land Survey	22	T29N R8W	H-9
		T R	
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

ANTRIM COUNTY MI. Register of Deeds Recorded

12-14-1999 13:40:44

Wanda R. Conway REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Terry B. Smith, in a field survey on Nov. 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Circa 1850 Retracement by C. E. Ostling 1971 certificate by B. Jones 1991 "set corner"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner established by C. E. Ostling missing Corner by B. Jones found measurements to east and west do not find that B. Jones corner is a reestablishment of Ostling retracement -- peer group findings -- establish corner at position as retraced by Ostling circa 1971

Ratified by Peer Group In accordance with P.O. 345 Antrim Co. Chairman

Arthur L. Lennox

Nov. 10, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Antrim County Monument at prorated distance between G-9 and I-9 14" double Elm N15W 36.33 6" DBL Elm N48W 44.80 UP North 58.06 14" W. Pine S40E 48.52 1/2" bar B. Jones S30°46'56"W 7.77



Signed by [Signature] Surveyor's Michigan License No. 25873

Date 12-14-1999