

JAN 27 2000

Liber 00003 Page 0085

SECTION

LAND CORNER RECORDATION CERTIFICATE ANTRIM COUNTY MI.  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Helena Twp.

Register of Deeds  
Recorded

12-14-1999 13:40:31

Manda R. Conway  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

<u>Antrim</u> (County)	Located In:	Corner Code #
1. Public Land Survey	23 T 29NR 8W	K-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Terry B. Smith, in a field survey on 11-18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Circa 1850
- F. Church 1914 found & perpetuated corner
- C. Ostling found 1/2" iron 1972

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found 1/2" bar per #12026 -- witnesses gone - measurements indicated this is a perpetuation of GLO corner  
excavation revealed remains of wood stake approximately 28" below surface

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set antrim county monument
- 6" Maple N35E 52.15
- 24" Maple N50E 34.08
- 10" Scotch Pine S55W 76.30
- 10" Elm N70W 60.75

Ratified by Peer Group  
In accordance with  
P.O. 345  
Antrim Co. Chairman

*Arthur L. Lennox*

Arthur L. Lennox  
Nov. 10, 1999



Signed by Terry B. Smith  
Surveyor's Michigan License No. 25873

Date 12-14-1999