

FEB 18 1999

184

Liber 00003 Page 0043

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Antrim

(County)

Located In: Elk Corner Code #
Rapids Twp.

- 1. Public Land Survey Sec. 28 T29NR9W E-11
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

ANTRIM COUNTY MI.
Register of Deeds
Recorded

12-28-1998 10:20:16

Manda R. Conway
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Neil L. Way, in a field survey on Dec. 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- Dec. 1856- GLO set post
- Oct. 1890- Church found bottom of old stake then set cedar stake and an old steel shod shoe
- Oct. 1989- B. Jones set 1/2" iron rod at fence intersection
- Oct. 1994- T. Smith found fence corner in swamp

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod as set by B. Jones at fence intersection

Ratified by peer group
in accordance with
P.O. 345
Antrim Co. Chairman

Arthur L. Lennox
Arthur L. Lennox
Nov. 18, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Antrim County Monument at iron rod at fence corner in 1' standing water
- West 0.50' fence corner post
- N70°E 17.50' Cedar stump
- South 21.90' Wild Cherry 8"
- S30°W 16.60' Tamarack 4"



Signed by *Neil L. Way*
Surveyor's Michigan License No. 28432

Date Dec. 17, 1998