

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 30 N.R. 5W
T. 30 N.R. 6W Antrim COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 18 - 13

CORNER MONUMENT Set 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 11-20-61

WITNESSES TO CORNER.....



5" Elm - S 60 E - 1.1 feet

4" H. Maple - S 40 W - 17.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this area. This corner also was set by proportionate measurement between the corner to Sections 13 - 24 - 18 - 19 and the 1/4 corner of 1 - 6. Longitudinal position established in accord with Heddon's record bearings. Falls in backslope on south side of meandering county road. Cannot identify only old BT's.

SURVEYOR'S SEAL

SIGNED Kenneth J. Bething DATE 11/21/61
REGISTERED LAND SURVEYOR