

REMONUMENTATION

FEB 22 1996

COMMISSION

STAR

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

DEC 6 9 22 AM '95

Wanda R. Conway
REGISTER OF DEEDS

For corners in

ANTRIM

(County)

Located In:

Corner Code #

1. Public Land Survey	T	30N	R	5W	E-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
E-3

GLO SET POST JULY 1839 ELM 10 N54E 11 SUGAR 12 N30W 14
CHURCH FND COR DEC 13, 1884 & OLD WIT'S IN GOOD CONDITION.
SUGAR 10 N15W 23
CHURCH VISITED COR JUNE 9, 1885. CHURCH VISITED COR OCT 16, 1885.
CHURCH VISITED COR JULY 21ST 1914 & DROVE IRON INTO TOP OF OLD
STAKE WITH STONES AROUND IT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-3

FND 5/8" X 24" IRON ROD WITH STONES AROUND IT IN CENTERLINE OF
INTERSECTION OF ROADS NORTH SOUTH & WEST IN HARMONY WITH CHURCHES
DESCRIPTION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-3

SET BERSTEN MONUMENT WITH CAP WITH IRON ROD & STONES BELOW.

N29E	1/2" REROD	49.08'	Ratified by Peer Group in accordance with P.O. 345: Chairman <i>[Signature]</i> Arthur L. Lennox Date: Oct. 26, 1995
S75W	POWER POLE	67.95'	
N67W	1/2" REROD	80.11'	
N02W	8" ELM	172.10'	



Signed by *[Signature]* Date 12-1-1995
Surveyor's Michigan License No. 28437