

MONUMENTATION

FEB 22 1996

COMMISSION

ANTRIM COUNTY
RECEIVED FOR RECORD

DEC 6 9 21 AM '95

Wanda R. Conway
REGISTER OF DEEDS

STAR
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ANTRIM

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>30N</u> | R | <u>5W</u> | <u>E-4</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, NEIL L. WAY, in a field survey on NOV. 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
E-4

GLO SET POST JULY 1839

SUGAR 10 S06E 08
LYNN 12 N21W 16

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-4

FOUND TWO 5\8" X 2" X 24" IRON BARS WITH ANGLE AT BASE SURROUNDED

STONES IN CENTERLINE OF ROAD INTERSECTION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4
SET BERSTEN MONUMENT WITH CAP WITH IRONS AND STONES BELOW.

Ratified by Peer Group	S75E 57.35'	SIGN POST
in accordance with	S70E 28.79'	SIGN POST
P.O. 345:	N30W 31.95'	SET 1\2" I. ROD
Chairman <i>Arthur L. Lennox</i>	S30W 28.93'	SET 1\2" I. ROD

Date: Oct. 26, 1995



Signed by *Neil L. Way*

Date 12-1-1995

Surveyor's Michigan License No. 28432