

FEB 22 1996

COMMISSION

STAR

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY
RECEIVED FOR RECORD

DEC 6 9 22 AM '95

Wanda R. Conway
REGISTER OF DEEDS

For corners in
ANTRIM
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>30N</u>	R	<u>5W</u>	<u>E-5</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5			●									
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-5

GLO SET POST JULY 1839

SUGAR 12 N55W 17
SUGAR 10 S68W 14

CHURCH SET CORNER OCT 1885 BY DOUBLE PROPORTION MEASUREMENT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-5

FOUND 3\4" X 24" PINCH TOP IRON PIPE AND EVIDENCE OF OLD WOOD STK 6' NORTH EAST OF CENTERLINE INTERSECTION ROADS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-5

SET BERSTEN MONUMENT WITH CAP WITH 3\4" IRON BELOW.

Ratified by Peer Group
in accordance with
P.O. 345:
Chairman *[Signature]*

Arthur L. Lennox

Date: Oct. 26, 1995

N45E 27.02' GUY POLE
S35W 53.67' R.PINE 10
S50W 53.15' R.PINE 10
S65W 7.41' 1" IRON ROD 18" DOWN



Signed by *[Signature]* Date 12-1-1995

Surveyor's Michigan License No. 28432