

MONUMENTATION

FEB 22 1996

COMMISSION

STAR
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

DEC 6 9 22 AM '95

Wanda R. Conway
REGISTER OF DEEDS

For corners in

ANTRIM

(County)

Located In:

Corner Code -#

- 1. Public Land Survey T 30N R 5W G-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, NEIL L. WAY, in a field survey on NOV. 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-3

GLO SET POST JULY 1839

**SUGAR 10 S22W 11
SUGAR 10 S87E 09**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-3

FOUND 3/4" SQUARE TOP BOLT 4' NORTH OF CENTERLINE OF TWO TRACK ROAD TO WEST AND ON LINE WITH FENCES TO NORTH AND SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-3

SET BERSTEN MONUMENT WITH CAP WITH SQUARE IRON BELOW.

Ratified by Peer Group	S17W 25.89' MPL 10
in accordance with	N50E 13.75' MPL 8
P.O. 345:	S70W 28.41' BSWD 10
Chairman <i>[Signature]</i>	N60W 25.60' MPL 8

Arthur L. Lennox
Date: Oct. 26, 1995



Signed by *[Signature]* Date 12-1-1995

Surveyor's Michigan License No. 28432

TRF 002 287

