

FEB 22 1996

COMMISSION

STAR  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

DEC 6 9 22 AM '95

Wanda R. Conway  
REGISTER OF DEEDS

For corners in  
**ANTRIM**

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	30N	R	5W	G-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, NEIL L. WAY, in a field survey on NOV. 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
G-4

GLO SET POST JULY 1839

MARKED A SUGAR 24 FOR CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4  
FOUND 3\4" X 24" I. PIPE IN CAST IRON PALE IN CENTERLINE OF TWO TRACK ROAD EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4  
SET BERSTEN MONUMENT WITH CAP WITH IRON PIPE BELOW.

Ratified by Peer Group  
in accordance with  
P.O. 345:  
Chairman Arthur L. Lennox  
Date: Oct. 26, 1995

S10E 20.96' MPL 6  
NORTH 13.67' MPL 8  
S10E 45.38' MPL 16  
S80W 69.59' BEECH 12



Signed by Neil L. Way Date 12-1-1995  
Surveyor's Michigan License No. 28432