

MEMORUMENTATION

FEB 22 1996

COMMISSION

STAR

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD
DEC 6 9 22 AM '95

Wanda R. Conroy
REGISTER OF DEEDS

For corners in
ANTRIM

(County)

Located In:

Corner Code #

| | | | | | |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 30N | R | 5W | G-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
G-5

GLO SET POST JULY 1839
BEECH 10 N13E 08
BEECH 10 S46W 18

LENNOX #28357 FOUND SPK AT FENCE CORNER WITH WITNESSES AND SET 3/4" IRON PIPE 4\11\1979.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-5

FOUND 3/4" IRON PIPE AND NAIL AT OLD FENCE CORNER REMAINS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-5

SET BERSTEN MONUMENT WITH CAP WITH 3/4" IRON BELOW.

| | | |
|----------------------------------|-------------|----------|
| Ratified by Peer Group | N53E 26.58' | BEECH 24 |
| in accordance with | N80E 11.36' | MPL 16 |
| P.O. 345: | N13E 18.85' | MPL 8 |
| Chairman <i>Arthur L. Lennox</i> | S50W 3.79' | MPL 4 |

Date: Oct. 26, 1995



Signed by Neil L. Way Date 12-1-1995

Surveyor's Michigan License No. 28432

002 284