

FEB 22 1996

COMMISSION

STAR
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

DEC 6 9 21 AM '95

Wanda R. Conway
REGISTER OF DEEDS

For corners in
ANTRIM
(County)

Located in: Corner Code #

1. Public Land Survey	T	30N	R	5W	H-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, NEIL L. WAY, in a field survey on NOV. 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
H-3

GLO SET POST JULY 1839

BEECH 12 S21E 19
SUGAR 14 N27E 48

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-3

FOUND 1 1/4" IRON PIPE AND JONES #23514 IRON IN CENTERLINE OF TWO TRACK ROAD TO EAST AND WEST AND ON LINE WITH FENCE TO SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-3

SET BERSTEN MONUMENT WITH CAP WITH IRON PIPE AND JONES IRON BELOW.

Ratified by Peer Group in accordance with P.O. 345:
Chairman Arthur L. Lennox
Date: Oct. 26, 1995

N75E 23.79' BSWD 8
S20W 6.20' MPL TW 14
N65W 20.26' BSWD 12
N23W 37.65' BEECH 14



Signed by Neil L. Way Date 12-1-1995

Surveyor's Michigan License No. 28432

FILED J02 PAGE 279