

FEB 22 1996

ANTRIM COUNTY MICHIGAN RECEIVED RECORD Nov 30 10 49 AM '95

LAND CORNER RECORDATION CERTIFICATE

COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970 STAR TWP

Wanda R. Conway REGISTER OF DEEDS

| FOR CORNERS OF--:  | LOCATED IN--: | CORNER CODE NUMBER |
|--|---------------|--------------------|
| 1. PUBLIC LAND SURVEY <u>11</u> T. <u>30</u> N. S., R. <u>5</u> E. W.      |               | <u>I-4</u>         |
| 2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.   |               |                    |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W. |               |                    |
| 4. LOT NO. _____, RECORDED PLAT _____                                      |               |                    |
| 5. PRIVATE CLAIMS _____  |               |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Terry B. Smith, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Oct 26, 1995, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Oct. 26, 1995 found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 1839 -- established 1/4 section post @ 40.00 chains  
 Sept. 30, 1975 H. Fluharty set 5/8" re-rod with cap @ intersection of roads N-S & W  
 recorded Liber 225 page 90 Antrim County Records.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 found 5/8" iron as described  
 replaced with Antrim County Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 W 1/4 Cor. Sec. 11, T30N, R5W  
 set Antrim County Monument  
 12" Maple N10E 22.80  
 10" Maple S70E 9.12  
 8" Db1. Maple S65W 25.70  
 16" Db1. Mpale N70W 30.00

Ratified by Peer Group in accordance with P.A.345  
 Chairman Arthur L. Lennox  
 Date: Oct. 26, 1995

SIGNED BY Terry B Smith DATE Nov. 29, 1995  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 25873

FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_