

MONUMENTATION

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

FEB 22 1996

Nov 30 10 49 AM '95

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Star Twp.

Wanda R. Conway
REGISTER OF DEEDS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>12</u> T. <u>30</u> N. <u>5</u> E. S., R. <u>5</u> W.		<u>L-5</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Terry B. Smith, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Oct 26, 1995, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 GLO 1839 -- established $\frac{1}{4}$ section post @ 40.12 $\frac{1}{2}$ chains

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 May 29, 1979 H. Fluharty set 5/8" iron equi-dist. & on fence to north, 4' north of center road recorded Liber 247 page 128 Antrim County Records. noted as restoration from County Surveyor's Records pages 100 and 101

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 S $\frac{1}{2}$ Cor. Sec. 12, T30N, R5W
 set Antrim County Monument
 24" Maple N35E 7.05
 20" Maple N78E 23.05
 16" S30E 34.10
 20" Maple S25W 36.25
 14" Maple N25W 46.90

Ratified by Peer Group in accordance with P.A. 341
 Chairman Arthur L. Lennox
 Arthur L. Lennox
 Date: Oct. 26, 1995


SIGNED BY Terry B. Smith DATE Nov. 29, 1995

SURVEYOR'S MICHIGAN REGISTRATION NO. 25873

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 002 271